SHREE GANESH ENTERPRISES
NEW DELHI · AMC MEP 24x7 · sge.org.in

DOC: SGE-EB-2026-08

E-BOOK 08 PRACTITIONER EDITION

Fire NOC & Building Approval Playbook

Requirements, Documents, Inspection Readiness and Common Rejection Reasons




FIG 08.1 — FIRE TENDER 6M DRIVEWAY, SETBACK & NOC SUBMISSION PLAN

SYLLABUS
10 Structured Chapters

CALCULATIONS
Worked SI Examples & Tables

SITE READY
Forms & Hinglish Glossary

Shree Ganesh Enterprises (SGE) — AMC MEP 24x7
Fire Fighting · Fire Alarm · Electrical · Plumbing · HVAC · IBMS · AMC

1st Edition, 2026
sge.org.in/ebooks/fire-noc-building-approval-playbook

Fire NOC & Building Approval Playbook

Requirements, Documents, Inspection Readiness and Common Rejection Reasons

A field playbook for navigating Indian Fire NOC and building approvals across residential, commercial, hospital, and industrial developments—exposing why paper-only compliance creates fatal liabilities, organizing mandatory statutory binders, detailing area-by-area inspection readiness, fixing the top 15 rejection items, and providing a 100-point self-audit scorecard.

Intended Audience: Building owners, Resident Welfare Associations (RWAs), developers, hospital/school administrators, architects, and MEP project managers leading Fire Service walkthroughs.

Engineering Notice & Standards Policy

This publication is an educational and field-reference guide prepared by **Shree Ganesh Enterprises (SGE)**. It is **not** a substitute for a stamped project design, statutory approval, or the governing text of the National Building Code of India (NBC), Bureau of Indian Standards (BIS) codes, Indian Electricity Rules / CEA Regulations, or your State/Municipal Fire Service Bye-Laws. Standards are cited at document level; always verify the **current applicable edition**, manufacturer datasheets, and local amendments before design, procurement, testing, or certification.

Worked numerical examples across this book are illustrative engineering demonstrations. All design inputs, pipe friction factors, battery deratings, and protective clearances must be re-checked for project conditions by a competent licensed professional. High-voltage electrical testing, pump-room servicing, and gaseous fire suppression operations can be fatal if undertaken without qualified personnel, written Permits-to-Work, and Lockout-Tagout (LOTO) controls.

Roman-script Hindi/Hinglish site terms are included cleanly to assist execution teams; formal English engineering terminology governs contractual and code interpretations.

Copyright & Licensing

© 2026 Shree Ganesh Enterprises (SGE). All rights reserved. No part of this manual may be reproduced, redistributed, or resold publicly without written authorization. Licensed strictly for purchaser and internal engineering team reference.

Publisher: Shree Ganesh Enterprises (SGE) — AMC MEP 24x7 | **Web:** sge.org.in | **Support:** support@amcmep.in

Contents

01 Chapter 1: What a Fire NOC Is — And Why Paper-Only Compliance Fails

02 Chapter 2: Provisional NOC, Final NOC and Renewal Stages Explained

03 Chapter 3: The Complete Compliance File and Mandatory Document Checklist

04 Chapter 4: External Access, Yard Width, Refuge Areas and Staircases

05 Chapter 5: Pump Room, Tanks, Riser, Sprinkler and Alarm Audit Readiness

06 Chapter 6: Top 15 NOC Rejection Reasons and How to Fix Them Fast

07 Chapter 7: Specific Needs — Residential Societies, Hospitals, Schools and Commercial Malls

08 Chapter 8: Managing the Inspection Walkthrough Professionally and Timeline Planning

09 Chapter 9: 100-Point Self-Audit Scorecard & QR Asset Register Templates

10 Chapter 10: Cheat Sheet, FAQ and Bilingual NOC Glossary

What You Will Learn

- Understand Provisional vs Final NOC stages and why real physical readiness outweighs cosmetic paperwork
- Build a complete, indexed Fire Compliance Binder containing drawings, certificates, and test records
- Audit external fire-tender setbacks, unlocked escape staircases, refuge areas, shafts, and basements
- Run a live pre-inspection dry test across pump rooms, wet risers, ZCVs, and fire alarm panels
- Fix the 15 most frequent causes of Fire NOC rejection before the inspecting officer arrives
- Maintain hassle-free annual NOC renewals using a QR asset register and structured AMC calendar

Chapter 1: What a Fire NOC Is — And Why Paper-Only Compliance Fails

An Approval Stamp Does Not Extinguish a Real Fire

Across India, too many stakeholders ask consultants a dangerous question: *"We don't want heavy fire piping—just help us get the Fire NOC paper cleanly."*

That mindset has devastating real-world consequences. Fire tragedies in apartments, coaching centres, hotels, and hospital wards repeatedly show the same underlying pattern: missing secondary staircases, locked terrace exit doors, shut fire pump valves, dead diesel batteries, and unsealed cable shafts spreading toxic black smoke vertically within two minutes. A paper certificate locked inside a manager's drawer cannot spray water or guide sleeping occupants through dark smoke.

NOTE

Fire NOC applicability, building height/area thresholds, fee rules, and online inspection processes vary across States, Union Territories, and Municipal Development Authorities in India. This playbook is an educational preparation guide—always consult your local State Fire Service Act/Rules, NBC 2016 Part 4, and a competent licensed fire professional; this is not legal advice.

Paper-Only Shortcut Mindset	Real Life-Safety & NOC Readiness Mindset
Buying empty/expired extinguishers only during audit week	Maintained, tagged, refilled cylinders placed permanently along exit routes
Pumping domestic water up risers only on inspection day	Dedicated pressurized fire reserve running smoothly on AUTO 365 days
Installing disconnected plastic smoke detectors for photos	Commissioned addressable/conventional loop verified with smoke tester & battery backup
Locking terrace/stairwell doors against theft	Panic-bar unlocked exit doors opening strictly outward with illuminated EXIT signs

HINGLISH

Fire NOC (Anapatti Praman Patra) = sarkar ke fire vibhag dwara di jaane wali aag suraksha manzoori. Paper compliance = sirf kaagaz poora karna jabki site par system band pada ho (yeh jaanleva galti hai).

Chapter 2: Provisional NOC, Final NOC and Renewal Stages Explained

Three Milestones Across a Building's Life

1. **Stage 1 — Provisional Fire NOC (Plan Approval Stage):** Applied *before* basement/superstructure construction starts. The Fire Service scrutinizes proposed architectural setbacks, staircase widths, water tank

capacities, refuge areas, and active fire schematic proposals. Never revise staircase locations or floor areas mid-construction without revised fire clearance!

2. **Stage 2 — Final Fire NOC (Occupancy / Completion Stage):** Applied *after* MEP contractors complete full installation, hydrostatic testing, alarm interfacing, signage, and commissioning. The Inspecting Fire Officer physically verifies site hardware, witnesses pump/hydrant/alarm discharge tests, and reviews statutory certificates before granting Final Clearance.
3. **Stage 3 — Periodic Fire NOC Renewal (Ongoing Operations):** Commercial, hospital, educational, hotel, and residential high-rises must renew NOC periodically (e.g. every 1–3/5 years per State Fire Act rules), backed by periodic half-yearly/annual **Fire Audit & Form-B Maintenance Certificates** from authorized agencies.

> **HINGLISH**
> Provisional NOC = naksha pass karane ke samay milne wali pehli manzoori. Final NOC = poori building aur fire system ban kar test hone ke baad milne wala mukhya certificate.

Chapter 3: The Complete Compliance File and Mandatory Document Checklist

Never Let an Inspection Stall Because a Certificate Stayed in Email

Organize one physical tabbed **Fire Safety Master Binder** stored cleanly inside the ground floor Fire Command Centre / Admin Office:

- ☐ **Approved Architectural Plans & Provisional NOC Copy** (stamped set cleanly matching built site!).
- ☐ **As-Built Fire Fighting & Fire Alarm Drawings** signed off by project fire engineer / contractor.
- ☐ **Hydraulic & Water Tank Storage Calculations Sheet** showing UG/terrace capacity dimensions clearly.
- ☐ **Fire Pump Manufacturer Curve Data & Performance Test Certificates** (0%, 100%, 150% test logs).
- ☐ **Fire Door Test Certificates & Glazing Ratings** (manufacturer laboratory fire-rating documentation).
- ☐ **Hydrostatic Pressure Test Records** for wet risers, sprinklers, and buried yard ring mains.
- ☐ **Electrical Safety / CEIG Clearance & Lift Fitness Certificates** (showing essential power supply independence & lift fire homing!).
- ☐ **Extinguisher Refill & PESO/BIS Compliance Tags Inventory.**
- ☐ **Emergency Evacuation Plan Diagram & Trained Fire Warden / Mock Drill Roster.**

WORKED EXAMPLE 1

Staircase Capacity & Occupant Load Cross-Check (Illustrative). Before calling the officer, verify basic egress numbers cleanly against your approved plan. Suppose a commercial office floor has gross usable area **1,000 m2**. Using an illustrative assumed occupant load factor of **10 m2 per person** (confirm actual table value in NBC 2016 Part 4 for your exact occupancy!):

Total Design Floor Occupants = `1,000 m2 / 10 m2/person = 100 occupants per floor`. Suppose building provides two remote exits, each staircase **1.50 m clear width** (= 3 unit widths of 500 mm). At an illustrative stair capacity of ~50 persons per 500 mm width unit -> one 1.50 m stair supports ~150 persons; two stairs support ~300 persons total. Verdict: **300 exit capacity > 100 occupants**, and having 2 independent stairs prevents single-stair trapping! Also confirm no mezzanine storage narrowed the 1.50 m stair landing width!

Chapter 4: External Access, Yard Width, Refuge Areas and Staircases

Walk the Outside Perimeter First — Just Like the Fire Officer Does

Fire officers start judging a building at the **entry gate** before ever entering the lobby!

Exterior & Egress Pre-Inspection Checklist

☐ **Entry Gate Width & Overhead Wire Clearance:** Heavy hydraulic aerial ladder fire tenders need unobstructed entry gates (check gate width/height arches—decorative concrete/steel welcome gates often trap fire trucks outside!).

☐ **Clear Driveway Setbacks Around Building:** Remove parked cars, security cabins, diesel drums, or garden planters blocking turning corners or external fire-tender hardstand!

☐ **External Fire Brigade Inlet Accessible:** Mounted clearly facing road with glass intact, blank caps fitted, and bold signage (`FIRE BRIGADE INLET`).

☐ **Staircase Doors & Terrace Lock Rules:** Zero chains/padlocks blocking staircase doors or roof exit! Use approved push-bar panic hardware or glass-break key boxes where security monitoring is needed.

☐ **Zero Combustibles Inside Stairwell Shafts:** Remove old sofa sets, cardboard boxes, shoe racks, and inverter batteries parked beneath staircase landings!

☐ **Illuminated Exit Signs & Emergency Lights:** Unplug hallway breaker briefly to prove battery backup keeps stair treads lit cleanly!

☐ **Refuge Area Unobstructed:** Confirm high-rise refuge terraces carry unobstructed railings, emergency signage, and NO outdoor chiller units or locked storage partitions!

HINGLISH

Setback = building ke chaaron taraf chhodi gayi khuli sadak jahan fire brigade ki gaadi ghoom sake. Panic bar = andar se dhakka dene par turant khulne wala suraksha darwaza lock.

Chapter 5: Pump Room, Tanks, Riser, Sprinkler and Alarm Audit Readiness

Live Physical Verification 72 Hours Before Official Inspection

Never wait for the Fire Officer to turn a pump switch for the first time! Run a **full dress-rehearsal live test**:

1. Open UG Fire Tank manhole cover with flashlight -> Prove **full clean water level up to overflow invert**!
2. Walk pump house -> Verify panel selectors on **AUTO**, zero fault LEDs, dual diesel batteries showing healthy DC volts, fuel day tank full.
3. Have one assistant stand on **top floor landing valve** with a fire hose branch/pressure gauge -> Crack landing valve or open test header cleanly:
   - Watch Jockey start/stop cleanly.
   - Crack further -> Confirm **Main Electric Pump auto-starts promptly** and delivers steady residual pressure without surging!
   - Switch off electric incomer briefly (simulating power outage) -> Confirm **Diesel Engine cranks briskly inside 5 seconds** and restores pressure!
4. Trigger one remote floor **Manual Call Point (MCP)** + **Canned Smoke Sensor**:
   - Confirm FACP registers exact floor location, hooters blare loudly throughout floors, **lifts home to ground floor**, **AHUs trip off**, and **access mag-locks release open**!

Chapter 6: Top 15 NOC Rejection Reasons and How to Fix Them Fast

#	Common Site Defect Triggering Rejection	Practical Fast Remedy
1	Terrace exit door locked with padlock/chain	Fit outward-opening **Panic Bar** + door alarm switch
2	Pump control panel switched to MAN/OFF or diesel dead	Repair battery/charger, service injectors, strap selector on AUTO
3	Electrical/garbage clutter dumped inside fire staircase	Clear all shafts immediately; issue RWA/management written ban
4	Missing fire-stopping around riser shaft slab holes	Fill floor penetrations cleanly with tested fire-stop mortar/sealant
5	Sprinkler bulbs covered in ceiling primer paint or dust caps	Remove plastic dust caps; **replace** all painted heads
6	Basement exhaust fans/smoke extractors un-wired to fire panel	Wire dry control relay interface to trip supply AHU & start exhaust
7	Insufficient UG water tank capacity or shared domestic tap	Isolate domestic suction strictly *above* fire reserve top datum
8	Emergency battery lights dead in staircases	Replace aged batteries / failed self-contained LED packs
9	Pressure gauge broken / landing valves missing coupling washers	Fit calibrated glycerine gauges; stock complete RRL hoses + nozzles
10	Missing Glow-in-Dark directional EXIT signage & floor numbers	Fix bilingual photoluminescent signs at every turn and floor landing
11	Yard hydrant access blocked by parked vehicles/gardens	Repaint yellow **NO PARKING — FIRE LANE** zones + removable bollards
12	Unlabelled/expired portable fire extinguishers	Refill/hydro-test via authorized vendor; mount proper brackets
13	False ceiling void unprotected or detectors missing above tiles	Verify code height rule; fit void heads + wall Response Indicators
14	Built-up site layout altered significantly from Provisional plan	Prepare clean As-Built drawings & file formal revised sanction early
15	No trained site emergency team or outdated mock drill logs	Run recorded evacuation drill & designate trained floor fire wardens

HINGLISH

Fire-stopping = deewar ya chhat mein pipe/cable nikalne ke chhed ko aag-rodhi masale se pack karna taaki dhuan oopar ke floor par na ja sake.

Chapter 7: Specific Needs — Residential Societies, Hospitals, Schools and Commercial Malls

Tailoring Compliance to Real Human Risk

1. **Residential Societies (RWAs):** Highest vulnerabilities live inside **basements (EV scooter / car lithium battery charging strips, stacked furniture)**, **shaft electrical meter clutter**, and **children locking shaft/terrace exits**. Never allow ad-hoc EV charging sockets inside enclosed basements without dedicated breaker isolation, heat detection, and clear spacing!
2. **Hospitals & Nursing Homes:** Patients on ventilators/ICUs **cannot descend 6 flights of stairs!** Protect via **Horizontal Evacuation Compartments** (smoke-tight fire doors splitting every ward floor into Zone A & Zone B so beds wheel safely across), ultra-clean maintenance of suction oxygen gas shutoffs, and zero locked corridor grilles!
3. **Schools & Coaching Institutes:** Enlist zero-obstacle wide corridors, outward-swinging classroom doors, and frequent gentle daytime evacuation drills so panicked crushes never occur on narrow stairs.
4. **Commercial Malls & Kitchens:** Monitor restaurant exhaust hoods for thick combustible oil grease (requires wet-chemical hood suppression & clean duct access panels) and keep atrium water curtain deluge valves strictly open!

WARNING

Improper multi-plug strips powering lithium-ion e-scooters inside enclosed apartment lobbies or under staircases create intense rapid-toxic-gas fires right along the only escape route! Keep charging outside or in designated ventilated protected bays.

Chapter 8: Managing the Inspection Walkthrough Professionally and Timeline Planning

How to Conduct a Smooth Site Inspection

- Assign one knowledgeable **Technical Escort** holding master keys (pump room, terrace, shafts, FCC panel) + digital camera + As-Built printouts on a clipboard.
- Keep site technicians stationed discreetly inside Pump House and Fire Command Centre with clear two-way walkie-talkies so test demonstrations happen promptly without frantic running around!
- Never argue code opinions defensively—note any officer observations calmly on the audit sheet, confirm exact statutory clause, and share a time-bound rectification completion file promptly with photographs!

WORKED EXAMPLE 2

100-Point Pre-NOC Readiness Scorecard Check (Illustrative). Run your mock walk 1 week before officer arrival:

- **Section A — Escape & Passive Integrity (30 pts):** Stairs clear (10), Doors self-closing & unlocked (10), Refuge/Setbacks clear (10) -> Site scores `28 / 30`.
- **Section B — Water, Pumps & Hydrants (30 pts):** Tank full (10), Auto Pump Start Electric & Diesel (10), Risers & Hoses complete (10) -> Site scores `29 / 30`.
- **Section C — Detection, Alarm & Lighting (20 pts):** FACP loop zero faults (8), Interface Trips OK (6), Exit Signs & Lights OK (6) -> Site scores `17 / 20`.
- **Section D — Compliance Documentation (20 pts):** As-Built sets, Test Certs, Drill Logs -> Site scores `16 / 20`. **Raw Score = 90 / 100.** *Zero-Tolerance Rule:* Even if score is 95/100, **ONE locked exit door or ONE dead diesel pump = Automatic Site Hold** until cleared!

WORKED EXAMPLE 3

Annual NOC Renewal Calendar & AMC Budgeting (Illustrative). Plan annual compliance cleanly so zero penalties or lapsed insurance claims hit owners:

- **Every Month:** Visually inspect all extinguishers, exit signs, stair clearances, and pump AUTO mode; log inside binder.
- **Every Quarter:** Flow-test one floor ZCV drain + test smoke detectors in rotating zones; verify diesel fuel & battery health.
- **Every 6 Months:** Conduct full Building Evacuation Mock Drill + Test Lift Homing & HVAC Interlocks cleanly + Submit half-yearly audit returns where state mandates.
- **Every 12 Months:** Complete Annual Pump 3-Point Curve Check, recharge/rotate due extinguishers, verify electrical thermography/IR, and file clean NOC Renewal Application 60 days ahead of expiry!

Chapter 9: 100-Point Self-Audit Scorecard & QR Asset Register Templates

Printable Fire NOC Self-Audit Scorecard

Area Checked	Pass Condition Verified?	Action Owner	Target Fix Date	Final Status
Main Gate & 6m Perimeter Fire Road	[ ] Completely clear & unmarked obstructions	Security Head	_____	[ ] PASS
All Staircase Doors	[ ] Self-closing, unlocked outward swing	Facility Supv	_____	[ ] PASS
Underground Fire Water Tank	[ ] Full clear water up to overflow	Plumber / Tech	_____	[ ] PASS
Jockey, Main & Diesel Panels	[ ] All selectors **AUTO**, zero trip faults	Fire Tech	_____	[ ] PASS
Diesel Batteries & Day Tank	[ ] > 25V DC (on 24V bank) & > 75% Diesel	Pump Op	_____	[ ] PASS
Floor Hose Cabinets & Landing Valves	[ ] 2 hoses + nozzle inside + wheel intact	AMC Team	_____	[ ] PASS
FACP Panel & Floor Call Points	[ ] Zero open/earth faults; test key OK	ELV Tech	_____	[ ] PASS
Compliance Master Binder	[ ] Drawings, Curve Tests & Certificates filed	Admin Lead	_____	[ ] PASS

Digital QR-Code Asset Compliance Register Template

Modern facility managers stick weatherproof QR inspection tags across pumps, ZCVs, FACP, and extinguishers (linking directly to cloud maintenance platforms like SGE's **AMC MEP 24x7 One App**) eliminating fake paper tick-marks:

Asset QR ID	Asset Description & Location	Last Service Date	Next Hydro/Recharge Due	Assigned Technician	Digital Audit Link / Status
`SGE–EXT–014`	4.5 kg CO2 — LT Panel Room B1	//2026	//2027	_____	Active / Verified
`SGE–PMP–002`	Diesel Main Pump — Pump House	//2026	Weekly Churn Due	_____	Active / AUTO
`SGE–ZCV–005`	Floor 3 Sprinkler ZCV — Shaft 2	//2026	Quarterly Test	_____	Tamper Normal

Chapter 10: Cheat Sheet, FAQ and Bilingual NOC Glossary

Golden NOC Readiness Rules

1. **Apply Early, Build Strictly to Approved Drawing**, and update As-Built amendments formally.
2. **Safety First, Certificate Second:** Treat every stair padlock, faulty NRV, or silent battery as a live risk to families and staff, not an inconvenience.
3. **Maintain Clean Paper + Living Hardware:** Officers reject spotless files if pump gauges are broken, and reject running pumps if test certificates are missing.

Frequently Asked Questions (Building Owners & RWAs)

1. **Can our society skip AMC after receiving Final Fire NOC?** Never! NOC renewal depends on continuous operational maintenance, and building insurance claims routinely reject fire losses if valid maintenance logs and working pumps weren't maintained!
2. **Who signs the completion / half-yearly maintenance compliance certificates?** Depending on your State Fire Service rules, either an approved registered Fire Consultant / Licensed Agency / Architect—check your state notification portal directly.
3. **Do older buildings constructed 20 years ago still need fire retrofitting?** Many Indian states enforce minimum retroactive life-safety standards (extinguishers, hoses, detection, unobstructed stairs, refuge rules) for older occupied multi-storeys, hospitals, and coaching centers—consult your local Fire Office cleanly.
4. **Why did the fire officer reject our finished false ceiling floor?** Often missing floor fire-stopping inside shaft cutouts, painted sprinkler bulbs, or exit direction arrows facing toward dead ends instead of stairs!
5. **What if the road outside our narrow plot is less than standard fire-tender access width?** Discuss permissible setback/downcomer/height concessions upfront with a licensed architect and the Fire Service *prior* to buying property or starting work—do not construct blindly hoping for exemption later!
6. **Can basement parking hold EV charging stations under Fire NOC guidelines?** Yes when designed safely with proper thermal detection, isolated breakers/shunt trip linked to fire alarm, non-combustible mounting, adequate mechanical exhaust ventilation, and local utility/authority clearance!
7. **Does a hospital need pressurized lifts?** High-rise hospitals and towers require dedicated **Fireman's Lift** with independent essential supply, fire-rated shaft lobby doors, and fireman override key switch cleanly per code.
8. **What happens if Fire NOC lapses without timely renewal?** Municipal authorities may serve show-cause notices, disconnect utility supplies, revoke trade/hospital operating licenses, or levy statutory penalties.
9. **Are fire-door glass view panels allowed to use ordinary window toughened glass?** No—view panels in fire-rated doors must carry certified fire-rated wired/ceramic glazing matching the door's hour rating!
10. **How long does a typical Final Fire NOC inspection take?** Half a day to one full day on-site depending on building height and number of risers—prepare checklists cleanly so your team wastes zero hours finding keys!
11. **Why must every lift car display "Do Not Use During Fire" signage?** Standard passenger lifts can trap fleeing staff inside smoke shafts when power trips; stairs remain the primary vertical evacuation path.
12. **Can an external consultant help run our pre-inspection dry test?** Yes—SGE / AMC MEP 24x7 provides complete Pre-NOC Mock Gap Audits, pressure/alarm diagnostics, and rectification prior to official inspection.

Hindi–English Bilingual Glossary

English Term	Hinglish / Site Hindi	Operational Meaning
Fire NOC (No Objection Certificate)	Aag suraksha manzoori patra	Official statutory fire department clearance
Provisional NOC	Shuruati naksha manzoori	Pre-construction approval of fire plans
Final NOC	Antima chalu manzoori	Occupancy clearance post commissioning
Fire Audit / Renewal	Saalana ya 6-maahi janch	Periodic statutory inspection certificate
Exit Access / Stairwell	Surakshit bahar nikalne ki seedhi	Protected fire-rated vertical escape path
Panic Bar / Push Bar	Dhakka dekar khulne wala handle	Latched exit hardware opening with hand push
Dead-End Corridor	Band gali wala rasta	Hallway having escape in one direction only (strict limit!)
Hardstand	Fire gaadi khadi karne ki pakki jagah	Reinforced perimeter driveway carrying fire truck loads
Turning Radius	Badi gaadi ghumne ki jagah	Smooth curve clearing aerial ladder fire tenders
Horizontal Evacuation	Ek hi manzil par doosre hisse mein jana	Essential hospital strategy across compartment walls
Fireman's Lift	Fire brigade ke liye surakshit lift	Dedicated priority override elevator inside rated shaft
Fire Command Centre (FCC)	Mukhya fire control room	Ground floor hub housing FACP, PA, repeater & plans
Form B / Self-Declaration	Niyamit rakh-rakhav praman patra	Periodic licensed agency system fitness filing
Photoluminescent Sign	Andhere mein chamakne wala board	Glow-in-dark exit path directional sign
Emergency Lighting	Power fail par jalne wali light	Battery-backed corridor and stair lights
As-Built Drawing	Asli bani hui building ka naksha	Final executed installation drawings matching site
Shunt Trip	Door se breaker band karne wala coil	Remotely disconnects non-essential EV/kitchen power on fire
Dry Riser	Bina paani khali pipe (truck jodne ke liye)	Empty riser filled only by approaching fire brigade
Fire-Rated Glazing	Aag rokne wala vishesh sheesha	Certified glass withstanding high fire heat without bursting
Door Closer	Darwaza apne aap band karne wali machine	Hydraulic arm shutting fire doors firmly
Intumescent Seal	Garmi se phoolne wali patti	Strip expanding around door gaps blocking hot smoke
Occupant Load	Manzil par logon ki kul sankhya	Design person count driving stair & door width
Setback	Deewar aur plot boundary ka khula rasta	Open exterior strip surrounding building structure

English Term	Hinglish / Site Hindi	Operational Meaning
Encroachment	Raste mein kabza / saman rakhna	Unauthorized storage blocking fire roads or stairs
Mock Drill	Aag se bachav ka nakli abhyas	Planned timed practice evacuation & response test
Compliance Binder	Poori suraksha file	Organized folder of NOCs, tests, curves & logs

Fire NOC & Building Approval Playbook

A field playbook for navigating Indian Fire NOC and building approvals across residential, commercial, hospital, and industrial developments—exposing why paper-only compliance creates fatal liabilities, organizing mandatory statutory binders, detailing area-by-area inspection readiness, fixing the top 15 rejection items, and providing a 100-point self-audit scorecard.

COMPLETE 12-VOLUME SGE ENGINEERING LIBRARY

01 Fire Fighting System A to Z
02 Fire Protection Design Handbook
03 The Fire Pump House Manual
04 Pressure Switch & Pump Controller Field Manual
05 Sprinkler System Design Workbook
06 Fire Alarm Design & Cable Calculation Guide
07 Special Hazard Suppression Guide
08 **Fire NOC & Building Approval Playbook**
09 Fire Extinguishers, Home & Office Safety
10 Cable Sizing, LT Panel & Short-Circuit (kA) Guide
11 HT Cable Hi-Pot Testing & Fault Location
12 The Site Engineer's Calculation Handbook

Need This Executed or Audited on Your Site?

Shree Ganesh Enterprises (SGE) designs, supplies, installs, tests, commissions, and maintains Fire Fighting, Addressable Fire Alarm, HT/LT Electrical, Plumbing, HVAC, and IBMS systems — backed 24×7 by AMC MEP 24x7.

Desk: +91 98719 36847 | +91 85273 78555 | **Web:** sge.org.in/tools | **Email:** support@amcmep.in